

PROPOSED FLOOR PLAN

SCALE: 1/4"=1'-0"

TEMPERATED GLAZED SHALL BE INSTALLED IN HAZARDOUS LOCATION ACCORDANCE R308.4

R302.5.1 Opening protection. Openings from a private garage directly into a room used for sleeping purposes shall not be permitted. Other openings between the garage and residence shall be equipped with solid wood doors not less than 1-3/8 inches (35 mm) in thickness, solid or honey-comb-core steel doors not less than 1-3/8 inches (35 mm) thick, or 20-minute fire-rated doors, equipped with a self-closing device.

LEGEND

LIGHT & FAN W/ SWITCH PENDANT LIGHT EXTERIOR WALL MOUNTED LIGHT RECESSED LIGHT AFC OUTLET GFI OUTLET CARBONE MONOXIDE DETECTOR SMOKE DETECTOR PROP. EXHAUST FAN 50 CFM EX.ELECTRICAL PANEL PROP. 2x4 WOOD FRAMING EX. WALLS TO REMAIN EX. 8" BLOCK WALL TO BE REMOVED DENOTES | #5 VERTICAL REBAR

> FLOWTHRU CALCULATIONS: NEW DEN AND RESTROOM AREA TOTAL AREA Flowthru area required = 1sq inch per 1sq ft, therefore:

Flowthru area required = 275 sf x 1sq inc/ 1 sf = 275 sq. inch

8"x16" openings provides 96 sq inch net open area. 8"x16" flow thru (96 sq inch) required = 275 sq. inch / 96 sq. inch = 3 Flow thru

Provide (4) 8"x16" flow thrus with louvers

Flow thru: 8"x6" Opening w/ louvers protection

## FBC 2020 APPROVED PRODUCTS LIST

			Σ. χ.			
PRODUCT CATEGORY	SUB CATEGORY	MANUFACTURER	STATE OF FLORIDA APPROVAL NUMBER	APPROVED DATE	DESCRIPTION	DESIGN PRESSURE RATING
Exterior Doors	Swinging Exterior Door Assemblies	MANSONITE	FL 22513.6	11/17/2020	Wood-edge Steel Side-Hinged Door Unit, 6'-8"  Opaque I/S or O/S Single Door	+70.0/ -70.0
Exterior Doors	Swinging Exterior Door Assemblies	THERMA-TRU CORPORATION	FL 20468.8	10/13/20	Nominal 6'8 "Impact" Glazed Composite Edge Fiberglass SingleDoor with Sidelite(s) (Inswing/Outswing; XO, OX or OXOconfigurations)	+47 psf/-50 psf
Exterior Doors	Swinging Exterior Door Assemblies	THERMA-TRU CORPORATION	FL 20468.9	06/08/2021	Nomincl 6'8 "Impact" Glazed Composite Edge Fiberglass Double Door Inswing/Outswing; XX orX00X configuration), 6'-0 x 6'-8" IMPACT RESIST.	+47 psf/-50 psf
Exterior Doors	Sliding Exterior Door Assemblies	PGT Industries	FL 251.9	11/24/20	SGD-5570 (Large Missile Impact) Vinyl Sliding Glass Door	+100 psf/-100 psf
Windows	Single Hung	Silver Line Building Products Corp.	FL 14911.5	12/15/2020	V1 Series/70 Series (2127), IMPACT RESISTANCE	+55.0 / -60.0
Windows	Fix Windows	PGT Industries	FL 243.5	05/19/21	PW-5520 Vinyl, IMPACT RESISTANCE	+80psf/-110 psf
Windows	Horizontal Slider	JELD-WEN	FL 14090.3	11/24/2020	PREMIUM VINYL ATLANTIC Horizontal Slider (8200) 74" x 62" Insulated Glass (5/16 SGP Lam in — 3/16 Annealed out), IMPACT RESISTANCE	+50 psf/-55 psf
Roofing	Underlayment	GAF	FL 10626.1	12/15/20	Roof Underlayment for use in sloped system	-75 psf
Wall Panels	Soffit	AMERIMAX HOME PRODUCTS	FL 5896.1	10/13/20	12" perforated "V" Panel and 12" solid "V" panel Aluminum soffit	+50 psf/-50 psf
Windows	Mullion	Silver Line Building Products Corp.	FL 6067.3	12/15/2020	Series 7537, Structural Beam Mullion	N/A


BLDG PERMIT PLANS FILE Copy of Record

TO THE BEST OF MY KNOWLEDGE THESE PLANS AND SPECIFICATIONS COMPLY WITH THE APPLICABLE MINIMUM BUILDING CODES AND THE APPLICABLE FIRE SAFETY STANDARDS AS DETERMINED BY THE LOCAL AUTHORITY IN ACCORDANCE WITH CHAPTER 553.79(7)(d) AND CHAPTER 633, LAWS OF FLORIDA

THESE PLANS HAVE BEEN REVIEWED FOR ADEQUACY OF STRUCTURAL COMPONENTS AND SYSTEMS ONLY IN COMPLIANCE WITH

FEB 0 7 2024 TOWN OF LONGBOAT KEY OF 10 SHEETS

ELOW'S RESIDENCE 90 OLD COMPASS ROAD NGBOAT KEY, FL 34228 BIGEL 690 LONG




SCALE SHOWN

DRW BY JAA

2023-33

01/22/2024

JOB #



DENOTES | #5 VERTICAL REBAR IN FILLED CELL W/ GROUT @ 4' O.C. MAX., CORNERS AND WINDOWS OPENING SIDES

## FOUNDATION NOTES

A FOUNDATION SURVEY SHALL BE PERFORMED AND A COPY OF THE SURVEY SHALL BE ON THE SITE FOR THE BUILDING INSPECTOR'S USE, OR ALL PROPERTY MARKERS SHALL BE EXPOSED AND A STRING, STRETCHED FROM MARKER TO MARKER TO VERIFY REQUIRED SETBACKS.

1. SOIL:

1.1 MAXIMUM ALLOWABLE SOIL PRESSURE 2000 PSF. CONCRETE:

2.1 CONCRETE COMPRESSIVE STRENGTH AT 28 DAYS: 3,000 PSI (NORMAL WEIGHT). 2.2 REINFORCING BARS: ASTM A615 (GRADE 40).

2.3 WELDED WIRE FABRIC (WWF): ASTM A185.

2.4 DETAIL REINFORCEMENT IN ACCORDANCE WITH ACI 315. 2.5 CONCRETE COVERAGE OF REINFORCEMENT: FOOTINGS 3" BOTTOM AND SIDES. 2.6 EARTH SUPPORTED SLABS: (INCLUDING EXTERIOR WALK AND DRIVE SLABS 3

DEPTH OF SLAB. FIBERMESH MAY BE USED IN LIEU OF WWF AT CONTRACTORS 2.7 CONCRETING OPERATIONS SHALL COMPLY WITH ACI STANDARDS. 2.8 LAP SPLICE SHALL BE AS FOLLOWS: #5 BAR 25", #4 BAR 20", #3 BAR 15". 2.9 SOIL TO BE TREATED FOR TERMITES PER FBC 2020 (7TH EDITION) BUILDING,

1/2" THICK MIN., REINFORCED WITH 6 X 6 - W 1.4 X W 1.4 WWF AT MID -

SECTION 2304.12. SAWCUT CONTROL JOINTS 1" DEEP ON 18' GRID WITHIN 24 HOURS OF FINISHING. PROVIDE 4MIL MOISTURE BARRIER BETWEEN SLAB AND COMPACTED BUILDING PAD.

SLAB SHALL BE FLOAT-FINISHED-STAIN OR PAINT AT OWNER'S DISCRETION. TO THE BEST OF MY KNOWLEDGE THESE PLANS AND SPECIFICATIONS COMPLY WITH THE APPLICABLE MINIMUM BUILDING CODES AND THE APPLICABLE FIRE SAFETY STANDARDS AS DETERMINED BY THE LOCAL AUTHORITY IN ACCORDANCE WITH CHAPTER 553.79(7)(d) AND CHAPTER 633, LAWS OF FLORIDA

Copy of Record 31" LONG MIN #5 — BAR EPOXIED INTO CONC. #3 OR #4 REINFORCING BAR #3 & #4 LAP SPLICE 25" MIN. LAP 3/4" Ø X 5" DEEP HOLE-FILLED W/ SIMPSON "SET" #5 REINFORCING BAR #5 LAP SPLICE 36" MIN. LAP #6 REINFORCING BAR #5 RE-BAR RETROFIT DETAIL #6 LAP SPLICE ALL SPLICE MUST BE TIE WITH WIRE #5 REINFORCING BAR RECEIVED R 1 7/8" —— TOWN OF LONGBOAT KEY #5 STD. 90 HOOK


> LAPPING OF REINFORCEMENT N.T.S.

> > THESE PLANS HAVE BEEN REVIEWED FOR ADEQUACY OF STRUCTURAL COMPONENTS AND SYSTEMS ONLY IN COMPLIANCE WITH FBC 2020 (7th Edition)

FEB 0 7 2024

Planning, Zoning & Building


**BLDG PERMIT PLANS** 



RESIDENCE
MPASS ROAD
(EY, FL 34228

BRADENTON, FL. 34203 SCALE SHOWN 2023-33 JOB # DATE 01/22/2024 DRW BY JAA

10 SHEETS



JULIAN A AGUILAR N. PE# 71367, CA#29488 5010,60THNDR. E. BRADENTON, FL. 34203

SCALE SHOWN 2023-33 JOB # DATE 01/22/2024

DRW BY JAA SHEET

10 SHEETS

LEGEND

WISWITCH

LIGHT & FAN



G"x4' LED LIGHT FIXTURE
WITH 3-40 WATT BULBS SURFACE

MOUNTED

ELECTRICAL PANEL 200 AMPS

ELECTRICAL PLAN NOTES: 1. THIS PLAN ELECTRICAL LAYOUT IS IN ACCORDANCE WITH (NEC 2017).

> PROVIDE FOR 1-#5 VERTICAL REBAR ELECTRICAL. GROUND TO FOUNDATION STEEL PER CODE SERVICE ENTRANCE, PANEL BOARDS, AND DISCONNECTS; SQUARE D OR APPROVED EQUAL. VERIFY LOCATIONS WITH OWNER.

APPROVED EQUAL). CONDUIT FOR ALL EXTERIOR LOCATIONS.

4. CONDUCTORS: NON-METALLIC SHEATHED CABLE- ALL COPPER (CITREX OR

5. PROPOSED 200 AMPS ELECTRICAL PANEL. ALL LOADS WILL BE VERIFIED BY A LICENSED ELECTRICAL CONTRACTOR.

6. FIXTURE INSTALLATION: TO BE COORDINATED WITH OWNER.

7. GROUND FAULT CIRCUITS PER CODE.

8. ALL WALL OUTLETS TO BE LOCATED @ 18 AFF. UNLESS OTHERWISE NOTED.

9. ALL OUTLETS AT KITCHEN CABINETS AT 48" AFF. UNLESS OTHERWISE NOTED.

10. ALL OUTLETS AT BATH VANITIES AT 36" AFF. UNLESS OTHERWISE NOTED.

11. ALL BOTTOMS OF SWITCHES AT 42" AFF. UNLESS OTHERWISE NOTED.

12. PROVIDE OUTLETS OR DEVICES AS REQUIRED BY CODES WHETHER SHOWN ON PLANS OR NOT.


13. ALL DUPLEX/SINGLE/GFI RECEPTACLES ARE TAMPER RESISTANCE.

14. ALL ELECTRICAL SWITCHES AND RECEPTACLES AT GROUND FLOOR SHALL BE LOCATED ABOVE OF FLOOD ELEVATION OR FINISH FLOOR WHICH IS GRATER.

15. ALL NEW OUTLES AND CIRCUITS FOR 15 AMPS AND 20 AMPS INCLUDING LIGHTING SHALL BE ARC FAULT CIRCUIT (AFC).

16. ALL GFI PROTECTION FOR APPLIANCES ARE NOTED AT THE RECEPTACLE. GFI RECEPTACLE MUST BE READILY ACCESSIBLE, AND CANNOT BE CONCEALED BEHIND APPLIANCES, PER NEC210.8. GFI PROTECTION MUST BE PROVIDED ELSEWHERE ON THE CIRCUIT. SUCH AS THE BREAKER.

17. WALL RECEPTACLE LAYOUT MUST COMPLY WITH NEC210.52(A) SO THAT NO POINT ALONG THE WALL IS MORE THAN 6' FROM A RECEPTACLE (MAXIMUM 12' BETWEEN RECEPTACLES).



FAN CFM

BRAND:

MODEL:

INTERNET:

DESCRIPTION:

CONTRACTOR SHALL REVIEW THESE DRAWINGS PRIOR FOR BIDDING AND/OR PERMITTING.

REFERENCE ONLY.

WORK PERFORMED USING THIS DESIGN.

INSTALLED BY ELECTRICAL CONTRACTOR

PERMITTING SHALL BE COVERED BY CONTRACTOR
THESE DRAWINGS ARE SCHEMATIC IN NATURE AND SHALL BE USED AS A

PURSUANT TO FLORIDA STATUES 2023 CHAPTER 471.003 SECTION (2) (H), THE LICENSED CONTRACTOR ASSUMES FULL RESPONSIBILITY FOR

LIGHTING FIXTURES SHALL BE SELECTED BY OWNER, FURNISHED AND

CARBON MONOXIDE DETECTOR:

KIDDE WIRE 120 Volts

Alarm w/ 9-Volt Backup

Interconnectable w/

50


KIDDE

# 21006406


# 202281774


TO THE BEST OF MY KNOWLEDGE THESE PLANS AND SPECIFICATIONS COMPLY WITH THE APPLICABLE MINIMUM BUILDING CODES AND THE APPLICABLE FIRE SAFETY STANDARDS AS DETERMINED BY THE LOCAL AUTHORITY IN ACCORDANCE WITH CHAPTER 553.79(7)(d) AND CHAPTER 633, LAWS OF FLORIDA

TOWN OF LONGBOAT KEY Planning, Zoning & Building THESE PLANS HAVE BEEN REVIEWED FOR ADEQUACY OF STRUCTURAL COMPONENTS AND SYSTEMS ONLY IN COMPLIANCE WITH FBC 2020 (7th Edition)



ELECTRIC PLAN
SCALE: 1/4"=1'-0"





CEILING VENTILATOR SCH	HEDULE
FANMARK: (EF-1) MANUFACTURER: FAN CFM	670 Broan 50

# MECHANICAL PLAN NOTES:

- 1. THIS PLAN SHOWS THE SCHEMATICH MECHANICAL LAYOUT ONLY. THE HVAC SYSTEM SHALL BE IN COMPLIANCE W/ FBC2020 MECHANICAL (7H EDITION).
- A LICENCED FLORIDA MECHANICAL CONTRACTOR HAVE DESIGNED THE COMPLETE SYSTEM THAT MEETS ALL APPLICABLE CODES.
- 3. HVAC SUBCONTRACTOR SHALL VERIFY LAYOUT, DUCT SIZE, ETC TO BE IN ACCORDANCE WITH FBC2020 MECHANICAL (7TH EDITION) AND ENERGY CONSERVATION (7TH EDITION).
- BLDG PERMIT PLANS 4. ALL DUCT MEASUREMENTS ARE INSIDE DIMENSIONS. ALL DUCT SHALL BE WRAP WITH R-5 INSULATION. Copy of Record
- EXISTING A/C EQUIPMENT TO REMAIN.

EXISTING A/C AREA =  $\pm 2234$  SF, ADDITION A/C AREA= $\pm 275$  SF REQUIRED A/C CENTRAL UNIT = 48000 BTU/HR SEER= 14.00 REQUIRED HEATER SYSTEM ELECTRICAL HEATER PUMP = 48000 BTU/HR HSPF= 8.2

FEB 0 7 2024

THESE PLANS HAVE BEEN REVIEWED FOR ADEQUACY OF STRUCTURAL COMPONENTS AND SYSTEMS ONLY IN COMPLIANCE WITH FBC 2020 (7th Edition)

SCALE SHOWN 2023-33 JOB # DATE 01/22/2024 TOWN OF LONGBOAT KEY Planning, Zoning & Building DRW BY JAA

10 SHEETS

RAISEDASEALL


DATE: 01/22×2024

JULIAN A AGUILAR N. FE#71367 CA#29488 5010 601H DR. E.

BRADENTON, FL. 34203

HVAC

TO THE BEST OF MY KNOWLEDGE THESE PLANS AND SPECIFICATIONS COMPLY WITH THE APPLICABLE MINIMUM BUILDING CODES AND THE APPLICABLE FIRE SAFETY STANDARDS AS DETERMINED BY THE LOCAL AUTHORITY IN ACCORDANCE WITH CHAPTER 553.79(7)(d) AND CHAPTER 633, LAWS OF FLORIDA



DESIGN DATA (ENCLOSED)

BASIC WIND SPEED: 160 MPH
WIND IMPORTANCE FACTOR: 1,0
RISK BUILDING CATEGORY: II
WIND EXPOSURE: D
CONSTRUCTION TYPE = V-B
INTERNAL PRESSURE COEFFICIENT (Cnet) SHALL BE
IN ACCORDANCE WITH TABLE 1609.6.2

DESIGN BEARING SOIL CAPACITY = 2000 psf

- I. VERIFY ALL ROOF TRUSS LOADS, SPANS AND LOCATIONS WITH ROOF TRUSS LAYOUT PROVIDED BY THE TRUSS MANUFACTURE COMPANY.
- 2. IN CASE OF ANY DISCREPANCY IN LOADS, SPANS OR LOCATIONS, THE ENGINEER OF RECORD SHALL TO REVIEW AND APPROVE THE NEW DESIGN PRIOR CONSTRUCTION.
- 3. THE INTENT OF THIS ROOF PLAN IS SCHEMATIC AND EXISTING, NOT ADDITIONAL WORK IS PROPOSED ON THE AREAS NO CALL OUT ON PLANS.

BLDG PERMIT PLANS FILE Copy of Record

FEB 0 7 2024
TOWN OF LONGBOAT KEY
Ranning, Zoning & Building

TO THE BEST OF MY KNOWLEDGE THESE PLANS AND SPECIFICATIONS COMPLY WITH THE APPLICABLE MINIMUM BUILDING CODES AND THE APPLICABLE FIRE SAFETY STANDARDS AS DETERMINED BY THE LOCAL AUTHORITY IN ACCORDANCE WITH CHAPTER 553.79(7)(d) AND CHAPTER 633, LAWS OF FLORIDA

THESE PLANS HAVE BEEN REVIEWED FOR ADEQUACY OF STRUCTURAL COMPONENTS AND SYSTEMS ONLY IN COMPLIANCE WITH FBC 2020 (7th Edition)

RAISED SEAL

CENS

DATE: 01/22/2024

JULIAN, A. AGUILAR N
PE# 71367 CA#29488

5010 60TH DR E


BRADENTON, FL. 34203

BIGEL 690 C LONG

OWNER AND A


| SCALE | SHOWN |
| JOB # 2023-33 |
| DATE | 01/22/2024 |
| DRW BY | JAA |
| SHEET |

10 SHEETS



WALL SECTIONS & DETAILS

RESIDENCE PASS ROAD 7, FL 34228



DATE: 01/22/2024 JULIAN A. AGUILAR N. RE# 71367 CA#29488 5010, 60TH, DR E BRADENTON, FL. 34203 2023-33

SCALE SHOWN JOB # 01/22/2024 DRW BY JAA SHEET

OF 10 SHEETS

4. Hydraulic cement conforming to ASTM C1157 Type GU, HE, MS, HS or MH.

The proportion of aggregate to cementitious materials shall be as set forth

5.Plaster (stucco) cement conforming to ASTM C1328.

in Table R702.1(3).

S

BIGE 69 AND

RAISED SEAL

DATE: 01/22/2024

JULIAN A. AGUILAR N. ORE# 71367 CA#29488

10 SHEETS

5010 60TH DR. E

BRADENTON, FL. 34203 SCALE SHOWN

2023-33 FEB 0 7 2024 01/22/2024 TOWN OF LONGBOAT KEY DRW BY JAA Planning, Zoning & Building

FILE

EXTERIOR OPENING FLASHING NOTE LExterior window and door openings. Flashing at exterior window and door openings shall extend to the surface of the exterior wall MASONRY WALL finish or to the water-resistive barrier complying with Section 703.2 for subsequent dramage. Mechanically attached flexible BRICK MOLD flashings shall comply with AAMA 712. Flashing at exterior window and door openings shall be installed in accordance with - PRE-HUNG DOOR FRAME one or more of the following: 1.1.The fenestration manufacturer's installation and flashing SHIM AS NECESSARY instructions, or for applications not addressed in the fenestration manufacturer's instructions, in accordance with the flashing TAPCONS PER DOOR MANUFATURER'S SPECS 2x4 P.T. BUCK STRIP FASTENED W/ ‡"X3-3/4 TAPCONS 12" O.C. & &

4" FROM EA END TO

MASONRY @ 12" O.C.

MIN. PLACE WITHIN 6"

FROM CORNERS

DOOR INSTALLATION

- MASONRY WALL

WINDOW FRAME

TAPCONS PER WINDOW MANUFATURER'S SPECS.

2x4 P.T. BUCK STRIP FASTENED W/ 4"X

3-3/4" TAPCONS @ 12" O.C. & 4" FROM EA END TO MASONRY @ 12" O.C.

MIN. PLACE WITHIN 6" FROM CORNERS

SEE GENERAL NOTES - SHEET 3 OF .

GENERAL REVISION NUMBER ONE RECESS TYPE DESIGNATION 8UB 11-4" THRU 14-0"

REVISION

WINDOW INSTALLATION

SCALE: 1/2"=1'-0"

SCALE: 1/2"=1'-0"

manufacturer's instructions. Where flashing instructions or details are not provided, pan flashing shall be installed at the sill of exterior window and door openings. Pan flashing shall be sealed or sloped in such a manner as to direct water to the surface of the exterior wall finish or to the water-resistive barrier for subsequent drainage. Openings using pan flashing shall incorporate flashing or protection at the head and sides.

Flashings shall be used to seal roofing systems, where the system is interrupted or terminated and shall be installed in a manner that prevents moisture from entering the wall and roof through joints in copings, through moisture permeable materials and at intersections with parapet walls and other penetrations through the roof plane.

Flashings shall be installed at wall and roof intersections, wherever there is a change in roof slope or direction and around roof openings. Where flashing is of metal, the metal shall be corrosion resistant with a thickness of not less than provided in Table R903.2.1 or in compliance with RAS 111.

Exception: Flashing is not required at hip and ridge junctions.

MATERIAL	TAL FLASHING MATE GAGE MINIMUM	GAGE	WEIGHT
MATERIAL	THICKNESS	0,102	(lbf)
	ITIONNESS		(101)
Copper	0.024		1 (16 oz)
Aluminum	0.024	A MODELLE	
Stainless steel	-	28	
Galvanized steel	0.0179	26	26
		(zinc coated	(zinc coated
		G90)	G90)
Aluminum zinc			
coated steel	0.0179	26	26
		(AZ50 alum	(AZ50 alum
zinc)	zinc)		
Zinc alloy	0.027		
Lead	-	2.5 (40 oz.)	
Painted terne			1.25 (20 oz.)

A cricket or saddle shall be installed on the ridge side of any chimney or penetration more than 30 inches (762 mm) wide as measured perpendicular to the slope. Cricket or saddle coverings shall be sheet metal or of the same material as the roof covering.

Exception: Unit skylights installed in accordance with Section R308.6 and flashed in accordance with the manufacturer's instructions shall be permitted to be installed without a cricket or saddle.

All membrane flashing shall be installed according to the roof assembly manufacturer's published literature.

KNOCK-OUT BLOCK W/(1) #5NOTCH LINTEL WHERE REQUIRED FOR CONCRETE PLACEMENT STD. 90 HOOK--PRECAST LINTEL W/ (1) #5 CONT. IN OPENINGS GRETER THAN 6'-0" WIDE 2X4 OR 2X6 BUCK STRIP DETAILS

NOTES:

90 HOOK DETAIL

VERTICAL REBAR FROM TOOTING

@ K.O. BLOCK.

CONTINUITY REINFORCEMENT

DOWEL FOR STEMWALL FOUNDATION

2 #5 REBAR

VERTICAL REINF. IN GROUTED CELI

CLEANOUT REQUIRED

2X4 PT PLATE

2X4 PT PLATE

TRUSS ANCHOR &

TRUSS (TYP.)

8" THICK CONCRETE MASONRY UNITS

COMBINED TIE BEAM/LINTEL

MIXED CONSTRUCTION

SCALE: N.T.S.

2X4 STUD AT 16" O.C.

- 8" CMU. WALL OR CONCRETE COLUMN

1/2" X 5-1/2" ANCHOR BOLT OR

EQ. @ 16" O.C. MAX. & 6" FROM

1/4" X 5-1/2" TAPCONS OR EQ. @

METAL MOISTURE BARRIER

\_\_\_ REINFORCED

BOND BEAM

PRE CAST

LINTEL

AT ROOF

FIN. FLOOR AND TOP OF WALL.

/ERTICAL WALL CONT. REINF.

25" MIN. LAP

1 #5 DWL.

25" MIN, LAP

GROUTED CELL

2 #5 REINF.


1. FILL LINTEL AND ALL CELLS ABOVE LINTEL.


-FILLED CELL W/ (1) #5

VERTICAL

2. VERIFY THAT ALL REINFORCEMENT HAS BEEN PLACED PROPERLY.

BLOCK WALL OPENING





TITLE: CAST-CRETE 8" LINTEL FABRICATION DETAILS FILE NAME: DBSUB2-14 DRAWN BY: CRAIG PARRINO, P.E. - REG. NO. 44756 SCALE: NOT TO SCALE DATE: 06/07/96 CHECKED BY: CRAIG PARRINO, P.E. - REG. NO. 44756 DRAWING No. FD8 SHEET 2 OF 3

633, LAWS OF FLORIDA

TO THE BEST OF MY KNOWLEDGE THESE PLANS AND SPECIFICATIONS COMPLY WITH THE APPLICABLE MINIMUM BUILDING CODES AND THE APPLICABLE FIRE SAFETY STANDARDS AS DETERMINED BY THE LOCAL AUTHORITY IN ACCORDANCE WITH CHAPTER 553.79(7)(d) AND CHAPTER

THESE PLANS HAVE BEEN REVIEWED FOR ADEQUACY OF STRUCTURAL COMPONENTS AND SYSTEMS ONLY IN COMPLIANCE WITH FBC 2020 (7th Edition)

CONTRACTOR TO VERIFY MANUFACTURED TRUSS PLAN PRIOR TO PLACEMENT OF STEMWALL OR MONOLITHIC FOOTING.

PLUMBER IS TO INFORM SUPERINTENDENT OF ANY VENTING WHICH UTILIZES A MASONRY WALL TO RESOLVE ANY POSSIBLE STRUCTURAL INTEGRITY ISSUES.

NO PENETRATIONS SHALL BE MADE IN ANY STRUCTURAL MEMBERS OTHER THAN THOSE LOCATED ON THESE DRAWINGS WITHOUT PREVIOUS APPROVAL FROM THE ENGINEER OF RECORD.

GARAGE DOORS SHALL SATISFY THE REQUIREMENTS OF FBC 2020 (7TH EDITION) FOR WIND LOADS AS DEFINED IN ASCE7-16

ALL OTHER JOB SPECIFICATION AND FINISH SPECIFICATIONS TO BE FURNISHED TO GENERAL CONTRACTOR BY THE HOME OWNER AND ARE NOT PART OF THESE DRAWINGS.

BRAND, STYLE, KIND, COLOR, ETC. OF ALL FINISHES & MATERIALS, ELECTRICAL FIXTURES, APPLIANCES, EQUIPMENT AS AGREED & NEGOTIATED BETWEEN OWNER & CONTRACTOR.

## MASONRY NOTES:

MASONRY CONSTRUCTION SHALL CONFORM TO THE REQUIREMENTS OF THE "SPECIFICATION FOR MASONRY STRUCTURES (ACI 530.1-02)", PUBLISHED BY THE AMERICAN CONCRETE INSTITUTE. SEE "TESTING AND INSPECTION NOTES" FOR ADDITIONAL INFORMATION.

HOLLOW LOAD-BEARING MASONRY UNITS SHALL CONFORM TO THE ASTM C-90, AND BE MADE WITH NORMAL WEIGHT AGGREGATE. UNIT COMPRESSIVE STRENGTH OF 1,900 PSI ON NET SECTION TO PROVIDE A MINIMUM NET AREA COMPRESSIVE STRENGTH OF MASONRY (pm) OF 2,500 PSI, AS DETERMINED BY THE STRENGTH METHOD OF ACI 530.1.

FILL ALL BOND BEAMS AND REINFORCED CELLS SOLIDLY WITH GROUT. GROUT SHALL CONFORM TO ASTM C-476 AND SHALL OBTAIN A MIN. 28 DAY COMPRESSIVE STRENGTH OF 2,500 PSI, TESTED PER ASTM C-1019 EACH 5,000 S.F. GROUT STOPS ARE TO BE MESHED OR SCREEN TYPE, FELT PAPER IS NOT ALLOWED.

REINFORCED STEEL SHALL BE IN ACCORDANCE WITH ASTM A-615, GRADE 60. SHOP FABRICATE REINFORCING BARS WHICH ARE SHOWN TO BE HOOKED OR BENT. DOWELS SHALL HAVE STANDARD 90 DEGREE HOOKS AND LAPPED WITH FIRST LIFT OF REINFORCING. PROVIDE A MINIMUM LAP OF 40 X BAR DIAMETER

MORTAR SHALL CONFORM TO ASTM C-270, TYPE M, S, OR N. ALL MORTAR SHALL MEET THE "PROPORTION SPECIFICATION" OF ASTM C-270 AND EVALUATED IN ACCORDANCE WITH ASTM C-780. UNLESS OTHERWISE INDICATED, ALL WALLS SHALL BE LAID IN RUNNING BOND. BOND CORNERS AND OTHER INTERSECTIONS OF ALL LOAD BEARING WALLS. INTERSECTING NON-LOADBEARING WALLS SHALL BE CONNECTED BY PREFABRICATED TEE AND CORNER HORIZONTAL JOINT REINFORCEMENT @ 16"O.C.

PROVIDE VERIDICAL REINFORCING BARS OF THE GIVEN SIZE AND SPACING AS INDICATED. PROVIDE BARS AT WALL CORNERS, INTERSECTION AND PEN EDGES, PROVIDE CLEAN OUTS FOR EACH GROUT POUR EXCEEDING 5FT.

PROVIDE PRECAST LINTELS ABOVE ALL WALL OPENINGS INCLUDING HVAC DUCTS. SEE DRAWINGS FOR LOCATIONS OF ALL OPENINGS. UNLESS OTHERWISE ON PLAN PROVIDE PRECAST LINTELS BELOW AS A MINIMUM.

-OPENINGS LESS THAN 6FT = 8" PRECAST U-LINTEL W/ 1-#5 & 8" KNOCK-OUT COURSE W/ 1-#5. (TYPICAL PERIMETER BOND BEAM 16" TOTAL DEPTH)

- OPENINGS GREATER THAT 6FT = SEE DRAWINGS. PROVIDE ONE REINFORCED CELL EACH SIDE OF OPENING W/ 8" LINTEL BEARING.

ALL WALLS OVER 8' HIGH MUST BE BRACED PRIOR TO POURING TIE BEAMS.

## FRAMING NOTES:

ALL DOOR HEADERS AT BEARING WALLS TO BE (2) 2X10 SYP OR BETTER, UNLESS NOTED OTHERWISE.

TRUSSES AND BEAMS SHALL BEAR DIRECTLY ON GLB OR SYP POSTS U.N.O. WHERE REQUIRED, SHIMS TO BE A36 STEEL U.N.O.

GLB OR SYP POSTS SHALL BEAR DIRECTLY ON CONCRETE SLAB OR ON SYP OR PT PLATE UNLESS NOTED OTHERWISE.

WOOD CONSTRUCTION, CONNECTIONS, AND NAILING SHALL CONFORM TO THE FBC 2020 (7TH EDITION).

ALL WOOD FRAMING MATERIALS SHALL BE SURFACE DRY AND USED AT 19% MAXIMUM MOISTURE CONTENT

ALL LOAD BEARING WALL FRAMING SHALL BE #2 SOUTHERN PINE. ALL JOIST AND RAFTER FRAMING SHALL BE #2 SOUTHERN PINE OR HEM-FIR.

ALL DOOR HEADERS AT BEARING WALLS TO BE (2) 2X10 SYP OR BETTER, UNLESS NOTED OTHERWISE.

PREFABRICATED METAL JOIST HANGERS, HURRICANE CLIPS, HOLD-DOWN ANCHORS AND OTHER ACCESSORIES SHALL BE MANUFACTURED BY SIMPSON STRONG TIE COMPANY OR EQUIVALENT. INSTALL ALL ACCESSORIES AS PER MANUFACTURERS REQUIREMENTS. ALL STEEL SHALL HAVE A MINIMUM THICKNESS OF 0.04 INCHES (ASTM A446 GRADE A) AND BE GALVANIZED(COATING G60).

BOLTHEADS SHALL BE CENTERED & DRILLED NO MORE THAN 1 16" LARGER THAN BOLT DIAMETER.

BOLTED CONNECTIONS SHALL BE TIGHT BUT NOT TO THE EXTENT OF CRUSHING WOOD UNDER WASHERS.

ALL NAIL SHANK SIZES TO BE MINIMUM OF 0.131 INCHES.

ALL FRAMING EXPOSED TO THE WEATHER OR IN CONTACT WITH MASONRY OR CONCRETE SHALL BE PRESSURE TREATED

MEMBERS DESIGNATED 'LVL' (E.G., 13/4" x 14" LVL) SHALL BE LAMINATED VENEER LUMBER AS MANUFACTURED BY LP (LP SolidStart LVL) OR ENGINEER APPROVED SUBSTITUTION. US BUILDING SUPPLY PREFERRED VENDOR 941.720.4245

CAST-IN-PLACE CONCRETE NOTES

CONCRETE MIXES SHALL BE DESIGNED PER ACI 30, USING PORTLAND CEMENT CONFORMING TO ASTM C-150, AGGREGATE CONFORMING TO ASTM C-33, AND ADMIXTURES CONFORMING TO ASTM C-494, C-1017, C-618, C-989 AND C-260. CONCRETE SHALL BE READY-MIXED IN ACCORDANCE WITH ASTM

CONCRETE SHALL CONFORM TO THE FOLLOWING COMPRESSIVE STRENGTH, SLUMP AND WATER/CEMENT RATIO REQUIREMENT:

IN ALL SALT ENVIRONMENTS A MIN. OF 5000PSI CONCRETE SHALL BE USED. (SLAB SHALL BE EXEMPT.) FOR OTHER ENVIRONMENTS USE 3000 PSI CONCRETE.

ALL CONCRETE WORK SHALL CONFORM TO ASTM ACI 301, "SPECIFICATION FOR STRUCTURAL CONCRETE BUILDINGS". HOT WEATHER CONCRETE SHALL BE IN ACCORDANCE WITH ACI 305.

ALL REINFORCING STEEL SHALL CONFORM TO ASTM A-615, GRADE 60.

ALL WELDED WIRE FABRIC (WWF) SHALL CONFORM TO ASTM A-185 (FLAT SHEETS ONLY).

ALL REINFORCED STEEL SHALL BE SET AND TIED IN PLACE PRIOR TO POURING OF CONCRETE, EXCEPT THAT VERTICAL DOWELS FOR MASONRY WALL REINFORCING MAY BE "FLOATED" IN PLACE.

REINFORCING STEEL INCLUDING HOOKS AND BENDS, SHALL BE DETAILED IN ACCORDANCE WITH ACI 315. ALL REINFORCING STEEL INDICATED AS BEING CONTINUOUS (CONT) SHALL BE LAPPED 40 X BAR DIAMETER. LAP CONTINUOUS BOTTOM BARS OVER SUPPORTS, LAP CONTINUOUS TOP BARS AT MID-SPAN UNLESS OTHERWISE NOTED.

UNLESS OTHERWISE NOTED, THE FOLLOWING MINIMUM CONCRETE COVER SHALL BE PROVIDED FOR REINFORCEMENT IN ACCORDANCE W/ ACI 318-02:

A. CONCRETE EXPOSED TO WEATHER: #6 THROUGH #18 BARS -2" #5 BAR, W31 OF D31 WIRE & SMALLER — 1½"

B. CONCRETE NOT EXPOSED TO EARTH OR WEATHER: BEAMS AND COLUMNS -11/2"

C. FOUNDATIONS EXPOSED TO EARTH -3" BAR SUPPORTS AND HOLDING BARS SHALL BE PROVIDED FOR ALL REINFORCING STEEL TO INSURE MINIMUM CONCRETE COVER. BAR SUPPORTS

SHALL BE PLASTIC TIPPED OR STAINLESS STEEL ALL EDGES OF PERMANENTLY EXPOSED CONCRETE SURFACES SHALL BE

FORMWORK SHALL REMAIN IN PLACE UNTIL CONCRETE HAS OBTAINED AT LEAST 90% OF ITS 28 DAY COMPRESSIVE STRENGTH. THE CONTRACTOR SHALL PROVIDE ALL SHORING AND RESORTING.

## ROOF FRAMING NOTES:

CHAMFERED 34" UNLESS OTHERWISE NOTED.

THE DESIGN OF ROOF FRAMING SHALL BE BASED ON THE REQUIREMENTS OF THE FLORIDA BUILDING CODE AND FBC-R 2020 (7TH EDITION).

DESIGN WIND LOADS SHALL BE APPLIED IN ACCORDANCE WITH ASCE 7-05. SEE WIND NOTES FOR WIND DESIGN REQUIREMENTS.

ROOF TRUSS MANUFACTURER SHALL SUBMIT AND PROVIDE COMPLETE LAYOUT AND FURNISH THE FOLLOWING INFORMATION: ROOF PITCH, LUMBER SIZE, SPACING, SPECIES AND GRADING, LOCATION AND MAGNITUDE OF UPLIFT

PRE-ENGINEERED TRUSS DESIGN SHALL BE SIGNED AND SEALED BY A FLORIDA LICENSED PROFESSIONAL ENGINEER.

ROOF SHEATHING SHALL BE 15/32" CD PLYWOOD OR EQ.

CONTRACTORS SHALL VERIFY WITH ROOF TRUSS PLAN PRIOR TO PLACEMENT OF FOOTINGS.

## SOIL NOTES:

ALL SOILS SHALL BE FREE OF DEBRIS AND ORGANIC MATERIALS AND COMPACTED TO 95% OF MODIFIED PROCTOR (ASTM D1557).

FOUNDATIONS SHALL BE BUILT ON UNDISTURBED SOIL OR PROPERLY COMPACTED FILL MATERIAL COMPLYING WITH THE 2020 (7TH EDITION).

STEM WALL FILL SHALL NOT EXCEED 12" LIFTS. SOIL BELOW FOOTINGS SHALL BE TESTED AND ALL SUBSEQUENT FILL SOILS IN LIFT NOT TO EXCEED 12" INTERVALS.

ALL FILL MATERIAL SHALL BE SP OR SM MATERIAL AS DEFINED BY THE UNIFORM SOIL CLASSIFICATION SYSTEM

ANY QUESTIONABLE SOIL SHALL BE REMOVED OR BROUGHT TO THE ATTENTION OF THE ENGINEER OF RECORD FOR EVALUATION.

SOIL BEARING CAPACITY IS BASED UPON 2,000 PSF.

WOOD GRADE STAKES ARE PROHIBITED.

### PEST/DECAY PROTECTION NOTES:

ALL PLANTINGS AND IRRIGATION/SPRINKLER SYSTEMS AND RISERS FOR SPRAY HEADS SHALL BE AT LEAST 1 FOOT FROM BUILDING SIDEWALLS.

SOIL TREATMENT SHALL MEET THE REQUIREMENTS OF 2020 (7TH EDITION) R320 METHOD.

WOOD GRADE STAKES SHALL NOT BE USED.

PROTECTION AGAINST DECAY AND TERMITES SHALL BE PROVIDED IN ACCORDANCE WITH 2020 (7TH EDITION) R319.

ROOF FLASHING SHALL BE PROVIDED IN ACCORDANCE WITH THE REQUIREMENTS OF 2020 (7TH EDITION) R703.7.5, R703.8, R903.2 & R905. TO THE BEST OF MY KNOWLEDGE THESE PLANS AND SPECIFICATIONS

## DESIGN LOADS AND NOTES:

55PSF W/ 1.33 STRESS INCREASE FACTOR, OR 45PSF W/ 1.25 STRESS INCREASE FACTOR, OR 41PSF W/ 1.00 STRESS INCREASE FACTOR.

FLOOR - LIVE LOADS

ASSEMBLY AREA BALCONY	-	100PSF
(FAMILY RESIDENCE OR <100 SF) ( >100 SF)		60PSF 100PSF
DINING ROOM AND RESTAURANTS OFFICE		100PSF
(CORRIDORS ABOVE 1ST FLOOR)	_	80PSF
(LOBBIES & 1ST FLOOR CORRIDORS)		100PSF
OFFICES	_	50PSF
RESIDENTIAL		10000
(UNINHABITABLE ATTICS WITHOUT STORAGE)		10PSF
(UNINHABITABLE ATTICS WITH STORAGE)		20PSF
(HABITABLE ATTICS & SLEEPING AREAS)		30PSF
(ALL OTHER AREAS EXCEPT BALCONIES) STAIRS		40PSF
(1 & 2 FAMILY DWELLING)	_	40PSF
(ALL OTHER)		100PSF
RETAIL STORES		
(FIRST FLOOR)	_	100PSF
(UPPER FLOORS)	_	75PSF
WHOLESALE STORES	_	125PSF

#### DL = 10PSF IN COMBINATION WITH WIND LOADS.

MEAN ROOF HEIGHT SHALL BE DETERMINED BY TRUSS DESIGNER FROM PLANS. LATERAL LOADS IN TRUSSES ARE RESISTED BY ROOF DIAPHRAGM AT POINT OF WIND LOAD INPUT UNLESS NOTED OTHERWISE.

TRUSSES MUST BE DESIGNED TO SUPPORT WALLS AGAINST OUT-OF-PLANE LOADS IN ACCORDANCE WITH ITEM 5.5. THIS APPLIES TO ALL TRUSSES WITH A RAISED HEEL CONDITION THAT BEAR ON AN EXTERIOR WALL.

TRUSS MANUFACTURER'S TRUSS LAYOUT SHALL SHOW ALL CONNECTIONS BETWEEN TRUSSES AND OTHER TRUSSES AND BETWEEN TRUSSES AND WOOD BEAMS.

ROOF TRUSS/ ROOF RAFTER CONNECTION TO DOUBLE TOP PLATE OR WOOD BEAM

USE SIMPSON H16 OR H16-2 AT EACH TRUSS WHERE POSSIBLE. PROVIDE ADDITIONAL TIEDOWNS FOR GREATER UPLIFTS.

WHERE THE H-16 CANNOT BE USED (EG. ON 3-PLY GIRDERS, AT CORNERS, ETC.) USE SIMPSON HTS16 AND ADDITIONAL TIEDOWNS TO MEET UPLIFT REQUIREMENTS.

PRE-ENGINEERED ROOF TRUSSES TO BE APPROVED BY ENGINEER OF RECORD.

#### FLOOR RAFTER/ I-JOIST/ CONVENTIONAL FRAMING CONNECTION TO DOUBLE TOP PLATE OR DIRECT BEARING ON WOOD BEAM

USE SIMPSON H2.5A AT EACH MEMBER (WITH OR WITHOUT UPLIFT) WHERE POSSIBLE. PROVIDE ADDITIONAL TIEDOWN'S FOR GREATER UPLIFTS.

PRE-ENGINEERED FLOOR TRUSSES/JOIST TO BE APPROVED BY ENGINEER OF

USE TRUSS HANGERS TO ATTACH FLOOR TRUSSES TO LVL BEAMS IF LESS THAN 3-1/2" SQUARE BEARING AREA IS PROVIDED.

RECORD.

### WINDOWS / DOORS

FOR ADDITIONAL TIEDOWNS AS REQUIRED.

EXTERIOR WINDOWS AND GLASS DOORS SHALL BE TESTED BY AN APPROVED INDEPENDENT TESTING LABORATORY AND BEAR AN AAMA, WDMA OR OTHER APPROVED LABEL IDENTIFYING THE MANUFACTURER, PERFORMANCE CHARACTERISTICS AND APPROVED PRODUCT EVALUATION ENTITY INDICATING COMPLIANCE WITH THE REQUIREMENTS OF THE FOLLOWING SPECIFICATION: ANSI/AAMA/NWWDA.

WINDOW AND DOOR ASSEMBLIES SHALL BE ATTACHED IN STRICT ACCORDANCE WITH THE PUBLISHED MANUFACTURER RECOMMENDATIONS TO ACHIEVE RESISTANCE TO APPROPIATE WIND SPEED WITH 3 SECOND DESIGN WIND GUSTS AND SHALL INCLUDE THE SPECIFICATION OF BUCK STRIP MATERIALS AND ANCHORING.

WOOD CRIBS ABOVE ARCHED WINDOWS SHALL COMPLY WITH DRAWING DETAIL CONTAINED HEREIN.


ALL SHIM MATERIALS SHALL BE MADE FROM MATERIALS CAPABLE OF SUSTAINING APPLICABLE LOADS, AND LOCATED AND APPLIED IN A THICKNESS CAPABLE OF WITHSTANDING THOSE LOADS.

THE DESIGN RESPONSIBILITY FOR THE INSTALLATION OF DOORS AND WINDOWS IS DELEGATED TO THE SPECIALTY ENGINEER OF THE MANUFACTURER AS REINFORCED WITH IN ALL TESTING DATA REQUIRED SUBMITTED IN CONJUNCTION WITH THIS

OPENING PERIMETERS HAVE BEEN DESIGNED TO TRANSMIT THE IMPOSED LOADS TO THE MAIN WIND FORCE RESISTING SYSTEM.

COMPLY WITH THE APPLICABLE MINIMUM BUILDING CODES AND THE APPLICABLE FIRE SAFETY STANDARDS AS DETERMINED BY THE LOCAL AUTHORITY IN ACCORDANCE WITH CHAPTER 553.79(7)(d) AND CHAPTER 633, LAWS OF FLORIDA

THESE PLANS HAVE BEEN REVIEWED FOR ADEQUACY OF STRUCTURAL COMPONENTS AND SYSTEMS ONLY IN COMPLIANCE WITH FBC 2020 (7th Edition)



DESIGN DATA

BASIC WIND SPEED: 160 MPH WIND IMPORTANCE FACTOR: 1.0 RISK BUILDING CATEGORY: II WIND EXPOSURE: D BUILDING: ENCLOSED

FULLY ENCLOSED BUILDING

INTERNAL PRESSURE COEFFICIENT (Cnet) SHALL BE IN ACCORDANCE WITH TABLE 1609.6.2 OCCUPANCY: R3

CONSTRUCTION TYPE: V-B 1. WIND LOADS ARE BASED ON A WIND VELOCITY OF 160 MPH APPLIED FOR A FULLY ENCLOSED STRUCTURE.

THIS BUILDING IS DESIGNED AS A FULLY ENCLOSED BUILDING BASED ON ALL OPENINGS BEING PROTECTED OR HAVING MISSILE IMPACT GLASS. 3. WIND DESIGN LOADS WERE DETERMINED BASED ON THE

FOLLOWING: BASIC WIND SPEED = 160 MPH, BUILDING CATEGORY II, IMPORTANCE FACTOR = 1.0 WIND EXPOSURE = D, INTERNAL PRESSURE COEFFICIENT =  $\pm 0.18$ .


DESIGN WIND PRESSURES FOR COMPONENTS AND CLADDING EXP=B\* POSITIVE PRESSURES = INWARD

NEGATIVE PRESSURES = OUTWARD (SUCTION)

ALL PRESSURE VALUES ARE IN PSF.

COMPONENT AREA (SQ. FT.)	ZONE 4	ZONE 5				
10	+46.1/-50.0	+46.1/-61.7				
20	+44.0/-47.9	+44.0/-57.5				
50	+41.2/-45.1	+41.2/-52.0				
100	+39.2/-43.1	+39.2/-47.9				
500	+34.3/-38.2	+34.3/-38.2				
		-				

\* FOR EXPOSURE D, MEAN ROOF HEIGHT= 22 HT, USE ADJUSTMENT FACTOR = 1.61



SHEATHING NOTES:

R803.2.2Allowable spans. The minimum thickness and span rating for wood structural panel roof sheathing shall not exceed the values set forth in Table R803.2.2.

TABLE R803.2.2 MINIMUM ROOF SHEATHING THICKNESS												
Rafter/Truss Spacing	WIND SPEED											
24 in. o.c.	115 mph	120 mph	130 mph	140 mph	150 mph	160 mph	170 mph	180 mph				
Minimum Sheathing Thickness, inches	7/16	7/16	7/16	7/16	15/32	19/32	19/32	19/32				
(Panel Span Rating) Exposure B	(24/16)	(24/16)	(24/16)	(24/16)	(32/16)	(40/20)	(40/20)	(40/20)				
Minimum Sheathing Thickness, inches (Panel Span Rating) Exposure C	7/16 (24/16)	7/16 (24/16)	15/32 (32/16)	19/32 (40/20)	19/32 (40/20)	19/32 (40/20)	19/32 (40/20)	23/32 (48/24)				
Minimum Sheathing Thickness, inches (Panel Span Rating) Exposure D	15/32 (32/16)	19/32 (40/20)	19/32 (40/20)	19/32 (40/20)	19/32 (40/20)	19/32 (40/20)	23/32 (48/24)	23/32 (48/24)				

R803.2.3.1Sheathing fastenings.

Wood structural panel sheathing shall be fastened to roof framing in accordance with Table R803.2.3.1. Where the sheathing thickness is 15/32 inches and less, sheathing shall be fastened with ASTM F1667 RSRS-01 (23/8" × 0.113") nails. Where the sheathing thickness is greater than 15/32 inches, sheathing shall be fastened with ASTM F1667 RSRS-03 (21/2" × 0.131") nails or ASTM F1667 RSRS-04 (3" × 0.120") nails. RSRS-01, RSRS-03 and RSRS-04 are ring shank nails meeting the specifications in ASTM F1667.

DROZ 2 3 1 DONE CHEATHING ATTACHMENT.

R803.2.3.1 ROOF SHEATH					WIND	SPE	FD								
Rafter/Truss Spacing	115 m	nph 120	mph	130				150	mph	160	mph	170	mph	180	mph
24 inc. o.c.	E F	E	F	E	F	E	F	Ε	F	Ε	F	E	F	E	F
Exposure B															
Rafter/Truss SG = 0.42		6	6	6	6	6	6	6	6	4	4	4	4	4	4
Rafter/Truss SG = $0.49$	6 1	2 6	12	6	6	6	6	6	6	6	6	6	6	6	6
Exposure C															
Rafter/Truss SG = $0.42$	6 6	6	6	6	6	4	4	4	4	4	4	3	3	3	3
Rafter/Truss SG = $0.49$	6 6	6	6	6	6	6	6	6	6	6	6	4	4	4	4
`			Е	xpos	ure D	)									
Rafter/Truss SG = $0.42$	6 6	6	6	4	4	4	4	4	4	3	3	3	3	3	3
Rafter/Truss SG = $0.49$	6 6	6	6	6	6	6	6	4	4	4	4	4	4	4	4
Rafter/Truss SG = 0.49	6 6	1	6		6	6	6		4	4		4			

0

RAISED SEAL DATE: 01/22/2024 JULIAN A AGUIEAR NO RE# 71367 CA#29488 5010, 60TH DR. E.

BRADENTON, FL. 34203 SHOWN SCALE 2023-33 JOB # 01/22/2024

DATE DRW BY JAA