MATCHLINE SEE SHEET 2

LEGEND:

- DENOTES VEGETATION
- DENOTES BOAT WITH DOCK
- DENOTES SAND SAMPLE LOCATIONS
- DENOTES SEAWALL
- DENOTES DOCK
- RED 16 — PROPOSED CHANNEL MARKER (SEE SHEET 17)
- PROPOSED CHANNEL
- DREDGE TO DENOTED DEPTH

CANAL 3

N = 1125898
E = 280285

N = 1126089
E = 280364

N = 1126069
E = 280369

DREDGE TO -3.4' NGVD
(-3.0' MLW)
DREDGING BY EXEMPTION

END DREDGING AT
MANGROVES BLOCKING
CANAL

TRIM MANGROVE
PER SHEET 17

10' BOTTOM WIDTH
BOX CUT 10B SHEET 16

JUAN ANASCO DRIVE

CANAL 4

RED 16

GREEN 15

DREDGE TO -5.4' NGVD
(-5.0' MLW)
DREDGING BY PERMIT

N = 1126216
E = 280742

20' BOTTOM WIDTH
SECTION 20A SHEET 15

N = 1126331
E = 280799

DREDGE SEDIMENT IN
VICINITY OF STORM
OUTFALL TO 5.4' NGVD
AS DIRECTED BY TOWN/
ENGINNER

DE NARVAEZ DRIVE

N = 1125409
E = 280638

15' BOTTOM WIDTH
BOX CUT 15A SHEET 16

I

I'

DREDGE TO -5.4' NGVD
(-5.0' MLW)
DREDGING BY EXEMPTION

N = 1125161
E = 280509

TRIM MANGROVE
PER SHEET 17

N = 1125375
E = 280616

CANAL 5

N = 1126049
E = 280957

BAYVIEW DRIVE

CANAL 6

NO DREDGING IN CANAL 6

50 0 50 100
SCALE IN FEET

COASTAL PLANNING & ENGINEERING, INC.
2481 N.W. BOCA RATON BOULEVARD
BOCA RATON, FLORIDA 33431
PH. (561) 391-8102
FAX (561) 391-9116
FLA. #G78775

PROJECT:
TOWN OF LONGBOAT KEY
NORTH CANAL MAINTENANCE
DREDGING PROJECT
PLAN VIEW

DRAWN BY: SB
CHECKED BY: DMES
DATE: 9/7/01
COMM. NO.: 8488.44
SCALE: 1" = 50'
SHEET: 3 OF 22

REVISION DATE:

G:\SARASOTA\LONGBOAT\8488S\CONSTRUCTION\LONGBOAT CANALS NORTH\8488SS NORTH EXEMPTION CANAL SURVEY.DWG